

NAME OF WORK : PROVIDING R.C.COVER SLAB TO THE EXISTING 'U' DRAIN AT AMAIDHI NAGAR

Item.No	Description of Items	Qty	Rate	Rate in words	Unit	Amount
1.CONCRETE WORK						
1.1	CODE NO. 4.5.5 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:3.6 (1 cement : 3 sand : 6 graded stone aggregate 20mm nominal size).	15.50 cum			1cum (One cubic metre)	
1.2	CODE NO. 4.9.1 Centring and shuttering including strutting, propping etc. and removal of form work for - foundations, footings, bases for columns.	125.50 sqm.			1sqm. (One square metre)	

Item.No	Description of Items	Qty	Rate	Rate in words	Unit	Amount
---------	----------------------	-----	------	---------------	------	--------

2.REINFORCED CONCRETE WORK

2.1	CODE NO. 5.19 Providing, hoisting and fixing upto floor five level precast reinforced cement concrete in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centring, shuttering, finishing smooth with 6mm thick cement plaster 1:3 (1 cement : 3 sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm nominal size).	9.00 cum			1cum (One cubic metre)	
-----	--	-------------	--	--	---------------------------	--

3.FINISHING

3.1	CODE NO. 13.24.1 6 mm cement plaster to ceiling of mix - 1:3 (1 cement : 3 fine sand).	220.00 sqm			1sqm (One square metre)	
-----	---	---------------	--	--	----------------------------	--

Item.No	Description of Items	Qty	Rate	Rate in words	Unit	Amount
	ROAD WORK					
	4.CULVERTS					
4.1	CODE NO. 7.6C Steel reinforcement for R.C.C. works including bending, binding and placing in position - Thermo Mechanical Treated Bars (TISCON / VIZAG / IISCO / SAIL).	1.13 Tonne			1Tonne (One Tonne)	