

NAME OF WORK: IMPROVEMENT TO THE BURIAL GROUND TO KUPPAM COLONY

DESCRIPTION	QUANTITY	RATE IN FIGURES	RATE IN WORDS	UNIT	AMOUNT
1. EARTH WORK					
ITEM NO. 1.1 CODE NO. 2.3.1A Supplying and filling with good earth (excluding rock) in layers not exceeding 20cm in depth, breaking clods, watering, rolling each layer with 1/2 tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes capacity including all leads and lift (payment will be made based on level measurement).	45.00 cum			1cum (one cubic metre)	
ITEM NO. 1.2 CODE NO. 2.8.1 Earth work in excavation in foundation trenches or drains (not exceeding 1.5m in width or 10sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m. including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m - all kinds of soil.	15.00 cum			1cum (one cubic metre)	

DESCRIPTION	QUANTITY	RATE IN FIGURES	RATE IN WORDS	UNIT	AMOUNT
-------------	----------	-----------------	---------------	------	--------

ITEM NO. 1.3 CODE NO. 2.28 Supplying and filling in plinth with river sand under floors including, watering, ramming consolidating and dressing complete.	20.00 cum			1cum (one cubic metre)	
---	-----------	--	--	---------------------------	--

## 2. CONCRETE WORK

ITEM NO. 2.1 CODE NO. 4.5.3 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm nominal size).	8.50 cum			1cum (one cubic metre)	
--	----------	--	--	---------------------------	--

ITEM NO. 2.2 CODE NO. 4.5.5 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:3.6 (1 cement : 3 sand : 6 graded stone aggregate 20mm nominal size).	5.00 cum			1cum (one cubic metre)	
--	----------	--	--	---------------------------	--

DESCRIPTION	QUANTITY	RATE IN FIGURES	RATE IN WORDS	UNIT	AMOUNT
ITEM NO. 2.3 CODE NO. 4.5.10 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:5:10 (1 cement : 5 sand : 10 graded stone aggregate 40mm nominal size).	11.00 cum			1cum (one cubic metre)	
3. REINFORCED CEMENT CONCRETE					
ITEM NO. 3.1 CODE NO. 5.14.1 Centring and shuttering including strutting, propping etc. and removal of form for - foundations, footings, bases of columns etc. for mass concrete.	27.00 sqm			1sqm (one square metre)	
4. BRICK WORK					
ITEM NO. 4.1 CODE NO. 6.1.8 Brick work with bricks of class designation 35 in foundation and plinth in - cement mortar 1:4 (1 cement : 4 sand).	8.00 cum			1cum (one cubic metre)	
ITEM NO. 4.2 CODE NO. 6.1.10 Brick work with bricks of class designation 35 in foundation and plinth in - cement mortar 1:6 (1 cement : 6 sand).	20.00 cum			1cum (one cubic metre)	

DESCRIPTION	QUANTITY	RATE IN FIGURES	RATE IN WORDS	UNIT	AMOUNT
ITEM NO. 4.3 CODE NO. 6.3 Extra for brick work in superstructure above plinth level upto floor five level.	20.00 cum			1cum (one cubic metre)	
5. FINISHING					
ITEM NO. 5.1 CODE NO. 13.8.2 12 mm cement plaster of mix - 1:4 (1 cement : 4 fine sand)	20.00 sqm			1sqm (one square metre)	
ITEM NO. 5.2 CODE NO. 13.8.3 12 mm cement plaster of mix - 1:5 (1 cement : 5 fine sand).	88.00 sqm			1sqm (one square metre)	
ITEM NO. 5.3 CODE NO. 13.9.2A 15 mm cement plaster on the rough side of single or half brick wall of mix - 1:5 (1 cement : 5 fine sand).	81.00 sqm			1sqm (one square metre)	
ITEM NO. 5.4 CODE NO. 13.73.2 Colour washing such as green, blue or buff to give an even shade - new work (two or more coats) with a base coat of whitening.	168.00 sqm			1sqm (one square metre)	